

Construction Certificate

Pursuant to Part 6 of the Environmental Planning & Assessment Act 1979

| Certificate No. | CC-23131 | | |
|----------------------------------|---|--|--|
| Type & Determination | Building Work | Approved | |
| Date of Determination | 01.09.2023 | | |
| + Subject Land | | | |
| Lot + DP | Lot 5 | DP 1285305 | |
| | Lot 7 | DP 1291562 | |
| Address | 788-804 & 806-824 Mamre Ro | oad, Kemps Creek | |
| Local Government Area | Penrith City Council | | |
| + Applicant | | | |
| Name | Daniel Brook | | |
| Company | Mirvac Industrial Developmen | ts Pty Ltd | |
| Address | Level 28, 200 George Street, | Sydney NSW 2000 | |
| Contact Details | Phone: 0421 128 584 | Email: <u>daniel.brook@mirvac.com</u> | |
| + Owner | | | |
| Name | Mirvac Funds Management Li | imited ATF Mirvac Kemps Creek Trust | |
| Address | C/- Level 28, 200 George Stre | · | |
| Contact Details | Phone: 0421 128 584 | Email: daniel.brook@mirvac.com | |
| + Description of Development | | | |
| Description | The proposed development involves the construction of Warehouse 1 within the Aspect Industrial Estate with ancillary offices, carparking, hardstand and landscaping. Warehouse 1 – CC2: Building services, all external works, office fit-out, facade excluding warehouse racking fit-out only. | | |
| | above only. Separate Construct of any subsequent works. 2. This Construction Certificate e. | ficate has been issued for the building works described tion Certificate/s will be required prior to commencemen xcludes any external ancillary services, structures or civi horities, and excludes temporary ground anchors. | |
| BCA Classification | Class 5, 7b & 10b | | |
| Applicable BCA | National Construction Code 2022 Volume 1 – Building Code of Australia | | |
| Development Consent | SSD-10448 (24.05.2022), SSD-10448-MOD-1 (25.08.2022) & SSD-10448-MOD-2 (30.11.2022), SSD-10448-MOD-3 (02.03.2023) | | |
| Statutory Certification | Work completed in accordance with documentation accompanying the application for the certificate (with such modifications verified by the certifying authority as may be shown on that documentation) will comply with the requirements of the Environmental Planning & Assessment (Development Certification and Fire Safety) Regulation 2021 as are referred to in Part 6 of the Environmental Planning & Assessment Act 1979 | | |
| Approved Plans | Refer to Schedule 1 | | |
| Fire Safety Schedule | Refer to Schedule 2 | | |
| Conditions | Refer to Schedule 3 | | |
| + Details of Certifying Authorit | ÿ | | |
| Certifying Authority | Blackett Maguire + Goldsmith | Pty Ltd | |
| Accreditation Number | RBC00004 | | |
| Signature | Mart | | |
| Signed on Behalf of BM+G | Dean Goldsmith | | |
| | Registration Number: | BDC: 0141 | |
| | | ודוע.עם | |



Approved Plans

+ Architectural Plans prepared by SBA Architects PL

| + Drawing Number | + Rev | + Date | + Drawing Number | + Rev | + Date |
|------------------|-------|----------|------------------|-------|----------|
| GA100 | М | 22.08.23 | GA211 | G | 14.06.23 |
| GA110 | D | 22.08.23 | GA301 | G | 22.08.23 |
| GA120 | С | 23.05.23 | GA350 | В | 22.08.23 |
| GA210 | F | 14.06.23 | | | |

Document Relied Upon

In conjunction with the approved plans and specifications the following documentation was relied upon in issuing the Construction Certificate:

+ Documentation:

| + Item | + Documentation | + Prepared by | + Date |
|--------|---|---|---|
| 1. | CC Portal Application Form | Mirvac | 30.08.2023 |
| 2. | Email confirming IFSR will not be provided | FRNSW | 08.05.2023 |
| 3. | Letter confirming Road Occupancy License is not required | Richard Crookes Constructions | 11.04.2023 |
| 4. | Acoustic Design Statement | PWNA | 31.05.2023 |
| 5. | Architectural Design Statement | SBA Architects PL | 30.08.2023 |
| 6. | BOWS Plans | Force Fire & Safety PL | Jan & Mar 2023 |
| 7. | Civil Design Statement | AT&L | 23.05.2023 |
| 8. | Electrical Design Statement | Modcol PL | 22.05.2023 |
| 9. | Lift Design Statement | Schindler | 02.06.2023 |
| 10. | Mechanical Design Statement | Paramount Air Conditioning (Aust) PL | 04.04.2023 |
| 11. | Smoke Exhaust Plans | Fusion HVAC | 05.12.2022 |
| 12. | Certificate of Design – Mechanical | Fusion HVAC | 03.04.2023 |
| 13. | Structural Design Statement | Northrop | 29.05.2023 |
| 14. | Structural Plans (x60 sheets) | Northrop Consulting Engineers | 07.02.2023, 19.04.2023, 30.01.2023, 09.02.2023, 07.02.2023, 17.04.2023, 02.03.2023, 01.03.2023, 06.04.2023, 24.03.2023, 13.02.2023, 15.03.2023, 12.07.2022, 17.01.2022, 21.09.2022, |



| | | | 25.01.2023, |
|-----|--|---|---|
| | | | 02.06.2023, |
| | | | 28.03.2023 |
| 15. | Landscape Design Statement | Site Image Landscape Architects | 28.07.2023 |
| 16. | Retaining Wall Design Statement | United Crib Blocks Construction PL | 07.07.2023 |
| 17. | Smoke Exhaust Design Statement | Fusion Hvac | 29.07.2023 |
| 18. | Traffic Design Statement | Ason Group | 07.07.2023 |
| 19. | Letter confirming acceptance of Fire Safety Engineering Report | Mirvac | 29.05.2023 |
| 20. | Approval of External Walls | Department of Planning and Environment Planning Portal | Not dated |
| 21. | Evidence of Documentation available on Mirvac website | Mirvac | 06.07.2023 |
| 22. | Aconex correspondence – Performance Based Design Brief | Plan Project Management | 24.07.2023 |
| 23. | FP1.4 Performance Solution Report | SBA Architects | 31.07.2023 |
| 24. | Post Tensioning Plan | PTWorks Australia PL | 14.03.2023 |
| 25. | Retaining Wall Plans | United Crib Blocks Construction PL | 29.05.2023 |
| 26. | Certificate of Design - Glazing | AGS Sydney PL | 20.07.2023 |
| 27. | Certification of structural adequacy of post-tensioned floor slab design | PTWorks Australia PL | 07.07.2023 |
| 28. | Civil/Stormwater Plans – Retaining wall layout | AT&L | 22.03.2023 |
| 29. | Civil Design Statement + Plans | AT&L | 23.06.2023 |
| 30. | Email confirming approval of external walls | DPE | 23.05.2023 |
| 31. | Certificate of Design - Balustrades | Richard Crookes Constructions | 13.07.2023 |
| 32. | Performance Based Design Brief – JV3 Assessment | Northrop Consulting Engineers | 07.07.2023 |
| 33. | Retaining Wall Plans (x 9 sheets) | AT&L / Unitied Crib Blocks Construction PL | 22.03.2023, 29.05.2023, 08.05.2023, 26.05.2023 |
| 34. | Bushfire Hazard Assessment | Blackash Bushfire Consulting | 25.07.2022 |
| 35. | Design Certificate – Fire Services | Force Fire & Safety PL | 23.05.2023 |
| 36. | Performance Based Design Brief - Weatherproofing | SBA Architects PL | 28.07.2023 |
| 37. | Fire Engineering Report | Core Engineering Group | 18.04.2023 |
| 38. | Peer review of FEBQ | Innova Fire Safety Specialists | 22.08.2022 |
| 39. | Aconex response to peer review | Core Engineering Group | 24.08.2022 |
| 40. | Email confirming no further comments required to Core's response | Innova Fire Safety Specialists | 20.09.2022 |
| 41. | Fire Engineering Brief Questionnaire | Core Engineering Group | 06.02.2023 |
| 42. | Fire Services Certification | Innova Fire Safety Specialists | 19.01.2023 |
| 43. | External wall System Disclosure Statement | SBA Architects PL CSIRO | 16.01.2023 11.02.2016 |



| | Certificate of Test No. FNE11605 | AWTA Product Testing | 08.09.2009 |
|-----|--|------------------------------|--|
| | Test Report No. 7-568613-CV | AWTA Product Testing | 19.07.2012 |
| | Test Report No. 7-586147-CV | Branz | 28.10.2022 |
| | Test Report No. FC16154-02-1 | | |
| 44. | Email confirming FEBQ will not be provided | FRNSW | 20.07.2022 |
| 45. | Access Design Compliance Statement | MGAC | 24.08.2023 |
| 46. | Structural (Façade) Plans | Partridge Structural Pty Ltd | 06.2022, 16.03.2023, 24.04.2023, 28.06.2023 |
| 47. | Structural (Econda) Cartification | Dortridgo Structural Dtv/Ltd | 28.06.2023 |
| 47. | Structural (Façade) Certification | Partridge Structural Pty Ltd | 20.00.2023 |

Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021

Documentation relied upon as required by the Environment Planning & Assessment (Development Certification and Fire Safety) Regulation 2021:

+ Proposed Performance Solution Reports in Respect of a Fire Safety Requirement:

| Title of Report | Fire Engineering Report |
|------------------------------|-------------------------|
| Date of Report | 18.04.2023 |
| Reference No. + Version | F201772_FER_03 |
| Name of Fire Safety Engineer | Graham Morris |
| Accreditation No. | 3200 |

+ Plans and Specifications Relating to Relevant Fire Safety Systems:

| + Item | + Documentation | + Prepared by | + Date |
|--------|--|---|--|
| 1. | Design Endorsement Certificate – Mechanical Ducted Smoke Control System | Paramount Air Conditioning (Aust) PL | 29.07.2023 |
| 2. | Design Certificate – Fire Services – Fire sprinklers, FH & FHR Systems | Force Fire & Safety PL | 23.05.2023 |
| 3. | Sprinkler Plans numbered FS-000, 100, 101, 201, 202, 300 | Force Fire & Safety PL | 21.07.2022, 18.01.2023, 16.02.2023 |
| 4. | Hydraulic and Fire Engineering Design Statement | Sparks & Partners Consulting Engineers | 06.07.2023 |

Pursuant to section 22 of the EP&A(DC&FS) Regulation 2021, Blackett Maguire + Goldsmith Pty Ltd (RBC00004) is satisfied that the above plans and specifications correctly identifies both the performance requirements and the deemed-to-satisfy provisions of the Building Code of Australia.



+ Schedule 2 – Fire Safety Schedule

Part 10 of the Environmental Planning and Assessment Act (Development Certification and Fire Safety) Regulation 2021.

| Please note: | | | | |
|---|--|--|--|--|
| | | | | |
| + A fire safety Schedule must deal with the whole of the building not just part of the building | | | | |
| Please complete all sections in full using CAPITAL LETTERS | | | | |
| Section 1: Location of building | | | | |
| Address (Street No., Street Name, Suburb and Postcode) | | | | |
| 788-804 & 806-824 MAMRE ROAD, KEMPS CREEK | | | | |
| Lot No. (if known) CP/DP/SP No. (if known) Building name (if applicable | | | | |
| LOT 5 DP 1285305 AIE – WH1 – CEVA | | | | |
| Lot 7 DP 1291562 | | | | |
| | | | | |
| Section 2: Reissue of Fire Safety Schedule (Section 80A of the Regulation) | | | | |
| Not applicable – Fire Safety Schedule is not being re-issued. | | | | |
| Reissued Fire Safety Schedule (please state reason below) | | | | |
| | | | | |
| Reason for Reissue of Schedule | | | | |
| □ Original Schedule Lost or Destroyed □ Correction of errors or omissions. | | | | |
| | | | | |
| Section 3: Reference Details (Section 78 of the Regulation) | | | | |
| Reference Type Reference Number (if known) | | | | |
| CONSTRUCTION CERTIFICATE CC-23131 | | | | |
| Section 4: Fire Safety Measures for the building – excluding Critical Fire Safety Measures (Section 79 of | | | | |
| the Regulation) | | | | |
| | | | | |
| + Item No. + Fire safety measure + Minimum standard of performance | | | | |
| Current (Existing) | | | | |
| 1. NOT APPLICABLE | | | | |

| Proposed (New or Modified including section 84(6) of the Regulation) | | | |
|--|--|---|--|
| 1. | ALARM SIGNALLING EQUIPMENT | AS 1670.3 – 2018 | |
| 2. | AUTOMATIC FIRE SUPPRESSION SYSTEMS | BCA SPEC. E1.5 AS 2118.1 – 2017 FM GLOBAL DATASHEETS 2-0 & 8-9 F201772_FER_03, FIRE ENGINEERING REPORT, PREPARED BY CORE ENGINEERING GROUP, DATED 18.04.2023 | |
| 3. | BUILDING OCCUPANT WARNING SYSTEM ACTIVATED BY THE SPRINKLER SYSTEM | BCA SPEC. E1.5 CLAUSE 8 AS 1670.1 – 2018 CLAUSE 3.22 | |
| 4. | EMERGENCY LIGHTING | BCA CLAUSES E4.2 & E4.4 AS 2293.1 – 2018 | |
| 5. | EMERGENCY MANAGEMENT PLAN | AS 3745 – 2010 | |



| | | F201772_FER_03, FIRE ENGINEERING REPORT, PREPARED BY CORE ENGINEERING GROUP, DATED 18.04.2023 |
|-----|--|--|
| 6. | EXIT SIGNS | BCA CLAUSES E4.5, NSW E4.6 & E4.8 AS 2293.1 – 2018 |
| 7. | FIRE CONTROL CENTRES AND ROOMS | BCA SPEC. E1.8 |
| 8. | FIRE DOORS | BCA CLAUSES C2.12 & C2.13 AS 1905.1 – 2015 MANUFACTURER'S SPECIFICATION |
| 9. | FIRE HOSE REELS | BCA CLAUSE E1.4 AS 2441 – 2005 |
| 10. | FIRE HYDRANT SYSTEMS (EXTERNAL HYDRANTS) | BCA CLAUSE E1.3 AS 2419.1 – 2021 F201772_FER_03, FIRE ENGINEERING REPORT, PREPARED BY CORE ENGINEERING GROUP, DATED 18.04.2023 |
| 11. | FIRE SEALS | BCA CLAUSE C3.15 AS 1530.4 – 2014 & AS 4072.1 – 2014 MANUFACTURER'S SPECIFICATION |
| 12. | INSULATED SANDWICH PANELS | IPCA CODE OF PRACTICE VERSION 4.3 AS ISO 9705 – 2003 FM 4880 – 2017 F201772_FER_03, FIRE ENGINEERING REPORT, PREPARED BY CORE ENGINEERING GROUP, DATED 18.04.2023 |
| 13. | LIGHTWEIGHT CONSTRUCTION | BCA CLAUSE C1.8 AS 1530.4 – 2014 MANUFACTURER'S SPECIFICATION |
| 14. | MANAGEMENT IN USE PROCEDURES: NO STORAGE IS PERMITTED FOR A MINIMUM WIDTH OF 6 M ALONG THE WESTERN PORTION OF THE PERIMETER ACCESS PATH UNDER THE SUPER AWNING, WHICH IS TO BE LINE- MARKED AROUND THE PERIMETER OF THE NOMINATED ZONE. THE BUILDING OWNER MUST ALSO MAKE THE TENANT AWARE OF THE RESTRICTION IN ANY LEASING DOCUMENTS. | F201772_FER_03, FIRE ENGINEERING REPORT, PREPARED BY CORE ENGINEERING GROUP, DATED 18.04.2023 |
| 15. | PERIMETER VEHICULAR ACCESS | BCA CLAUSE C2.4 FRNSW FIRE SAFTEY GUIDELINE "ACCESS FOR FIRE BRIGADE VEHICLES AND FIREFIGHTERS" F201772_FER_03, FIRE ENGINEERING REPORT, PREPARED BY CORE ENGINEERING GROUP, DATED 18.04.2023 |
| 16. | PORTABLE FIRE EXTINGUISHERS | BCA CLAUSE E1.6 AS 2444 – 2001 |



| 17. | SMOKE HAZARD MANAGEMENT SYSTEMS SMOKE EXHAUST (ACTIVATED BY SPRINKLER SYSTEM) | BCA SPEC E2.2B AS/NZS 1668.1 – 2015 AS 1670.1 – 2018 F201772_FER_03, FIRE ENGINEERING REPORT, PREPARED BY CORE ENGINEERING GROUP, DATED 18.04.2023 |
|-----|--|---|
| 18. | SOLAR PANELS | F201772_FER_03, FIRE ENGINEERING REPORT, PREPARED BY CORE ENGINEERING GROUP, DATED 18.04.2023 |
| 19. | WARNING & OPERATIONAL SIGNS | BCA CLAUSES D3.6 AS 1905.1 – 2015 F201772_FER_03, FIRE ENGINEERING REPORT, PREPARED BY CORE ENGINEERING GROUP, DATED 18.04.2023 |



| Details of Fire Safety Building | Code of Australia (BCA) P | erformance Solutions Report(s) |
|---|-------------------------------------|---|
| + (Ref No./Title of report/Author/Date) | + BCA Performance Requirement(s) | BCA DtS Provision(s) and details of non- compliance |
| F201772_FER_03, FIRE ENGINEERING REPORT, PREPARED BY CORE ENGINEERING GROUP, DATED 18.04.2023 | CP9 | CLAUSE C2.4 – PERIMETER VEHICULAR ACCESS THE PATH IS GREATER THAN 18M FROM THE BUILDING ALONG THE SOUTHERN PERIMETER AND ASSOCIATED CARPARKS. IN ADDITION, THE PATH REQUIRES TRAVEL BENEATH THE SUPER AWNING ON THE WEST. |
| | DP4 & EP2.2 | CLAUSE D1.4, D1.5, E2.2 – EXTENDED TRAVEL DISTANCES & RATIONALISED SMOKE EXHAUST SYSTEM – WAREHOUSE: THE FOLLOWING NON-COMPLIANCES EXISTS WITHIN THE WAREHOUSE: EXTENDED TRAVEL DISTANCES OF UP TO: • AMBIENT SECTION: TRAVEL DISTANCES ARE UP TO 95 M TO THE NEAREST EXIT AND 190M BETWEEN ALTERNATIVE EXITS (INCLUDING TRAVEL BENEATH THE AWNINGS). • TEMPERATURE-CONTROLLED SECTION: TRAVEL DISTANCES ARE UP TO 85 M TO THE NEAREST EXIT AND 170 M BETWEEN ALTERNATIVE EXITS (INCLUDING TRAVEL BENEATH AWNINGS). • SUPER-AWNING TRAVEL: TRAVEL DISTANCES ARE UP TO 70 M TO THE NEAREST EXIT AND 140 M BETWEEN ALTERNATIVE EXITS. THE WAREHOUSE AREAS SHALL BE PROVIDED WITH RATIONALISED AUTOMATIC SMOKE EXHAUST SYSTEM. |
| | EP1.3 | CLAUSE E1.3 – FIRE HYDRANT DESIGN THE APPLICABLE HYDRANT STANDARD REVISION REFERENCED IN THE BCA 2019 AMDT 1 IS AS2419.1:2005. HOWEVER, THE HYDRANT SYSTEM FOR SUBJECT BUILDING IS DESIGNED IN ACCORDANCE WITH AS2419.1:2021. THE SCOPE OF AS2419.1:2021 DOES NOT INCLUDE BUILDINGS WITH A TOTAL VOLUME OF MORE THAN 108,000 M ³ . HOWEVER, THE STANDARD IS APPLIED, WITH ADDITIONAL MEASURES TO THIS BUILDING, WHICH EXCEEDS 108,000 M ³ . THE HYDRANTS UNDER THE EASTERN AND WESTERN AWNINGS OF THE ON-GRADE DOCKS ARE DESIGNED AS EXTERNAL HYDRANTS. |



| Details of Fire Safety Building Code of Australia (BCA) Performance Solutions Report(s) | | |
|---|-------------------------------------|--|
| + (Ref No./Title of report/Author/Date) | + BCA Performance Requirement(s) | + BCA DtS Provision(s) and details of non- compliance |
| | EP1.3 | CLAUSE E1.3 – HYDRANT BOOSTER LOCATION THE LOCATION OF THE HYDRANT BOOSTER IS NOT WITHIN SIGHT OF THE MAIN PEDESTRIAN ENTRANCE TO THE SOUTH- WESTERN MAIN OFFICE. |
| | EP1.4 | CLAUSE E1.5 – SPRINKLER BOOSTER LOCATION THE LOCATION OF THE SPRINKLER BOOSTER IS LOCATED ADJACENT TO THE TANK, WHICH IS LOCATED ALONG THE NORTHERN PERIMETER OF THE SITE, NOT BEING WITHIN SIGHT OF THE MAIN PEDESTRIAN ENTRANCE TO THE FACILITY (AT THE SOUTH-WESTERN CORNER), AND THEREFORE PRESENTS A TECHNICAL NON- COMPLIANCE WITH AS2118.1:2017 UNDER CLAUSE 4.14 ENTITLED "FIRE BRIGADE BOOSTER ASSEMBLY". |
| | EP1.4 | CLAUSE E1.5 – SPRINKLER SYSTEM DESIGN TO FM GUIDELINES THE RIDGE HEIGHT OF THE WAREHOUSE IS DESIGNED TO BE 16 M BY UTILISING ROOF- LEVEL SPRINKLERS ONLY (I.E. NO IN-RACKS) VIA CONFORMANCE WITH FACTORY MUTUAL GLOBAL DATASHEETS 2-0 AND 8-9, IN LIEU OF AS2118.1:2017. |

Section 5: Critical Fire Safety Measures - where applicable to the building (Section 79 of the Regulation)

Note: A critical fire safety measure is one where the performance is verified at intervals of less than 12 months through the submission of a supplementary fire safety statement.

| + Item No. | + Fire safety measure | | + Minimum standard of performance |
|----------------------------|-----------------------|--|-----------------------------------|
| Current (Existing) | | | |
| 1. | NOT APPLICABLE | | |
| Proposed (New or Modified) | | | |
| 1. | NOT APPLICABLE | | |

Section 6: Details of approved exemptions from compliance with BCA standards for a relevant fire safety system (Section 74 of the Regulation)

| + Item No. | + Relevant fire safety measures | + Description of exemption |
|------------|---------------------------------|----------------------------|
| 1. | NOT APPLICABLE | |

| Section 7: Name of authority or registered certifier issuing this schedule | |
|--|--------------------------------------|
| Name | Organisation (Business name) |
| DEAN GOLDSMITH | BLACKETT MAGUIRE + GOLDSMITH PTY LTD |
| Business Address (Street No., Street Name, Suburb and Postcode) | |
| | |

SUITE 2.01, 22-36 MOUNTAIN ST, ULTIMO NSW 2007



Registration Number (Where Applicable) **RBC00004 (BDC 0141)** Date of Issue **1/09/2023**



+ Schedule 3 – Conditions of Construction Certificate

There are no conditions pursuant to section/s 27, 22, 116 or 117 of the Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021 at the date of issue of this Construction Certificate.

Nil.



01 September 2023

The General Manager Penrith City Council PO Box 60 Penrith NSW 2751

Dear Sir/Madam

Re: DA No. SSD-10448 – 788-804 & 806-824 Mamre Road, Kemps Creek

As required by Section 13(2) of the EP&A (DC&FS) Regulation 2021 (The Regulation) notice is hereby given that the following application for Construction Certificate has now been approved.

| Applicant | Mirvac Industrial Developments Pty Ltd |
|-----------------|---|
| Subject Address | 788-804 & 806-824 Mamre Road, Kemps Creek |
| Project No. | 220022 |
| Date Received | 28.04.2023 |
| Date Determined | 01.09.2023 |

Please find undercover a copy of the Construction Certificate No. CC-23131 for the proposed CC2, as follows:

The proposed development involves the construction of Warehouse 1 within the Aspect Industrial Estate with ancillary offices, carparking, hardstand and landscaping. Warehouse 1 – CC2: Building services, all external works, office fit-out, facade, excluding warehouse racking fit-out only.

We have also enclosed a copy of the approved documentation and other documentation relied upon as indicated on the Construction Certificate following for Council's record.

Pursuant to Schedule 4 Item 9 of the EP&A Regulation 2021, a sum of \$44.00 for the submission of this Part 6 Certificate has been processed on the NSW Planning Portal.

Please contact the undersigned should you have any further enquiries on 02 9211 7777.

Yours sincerely,

Jackson Boyd Building Surveyor BM+G



01 September 2023

The Director – General The Department of Planning & Environment 12 Darcy Street Parramatta NSW 2150

Dear Sir/Madam

Re: DA No. SSD-10448 – 788-804 & 806-824 Mamre Road, Kemps Creek

As required by Section 13(2) of the EP&A (DC&FS) Regulation 2021 (The Regulation) notice is hereby given that the following application for Construction Certificate has now been approved.

| Applicant | Mirvac Industrial Developments Pty Ltd |
|-----------------|---|
| Subject Address | 788-804 & 806-824 Mamre Road, Kemps Creek |
| Project No. | 220022 |
| Date Received | 28.04.2023 |
| Date Determined | 01.09.2023 |

Please find undercover a copy of the Construction Certificate No. CC-23131 for the proposed CC2, as follows:

The proposed development involves the construction of Warehouse 1 within the Aspect Industrial Estate with ancillary offices, carparking, hardstand and landscaping. Warehouse 1 – CC2: Building services, all external works, office fit-out, facade, excluding warehouse racking fit-out only.

We have also enclosed a copy of the approved documentation and other documentation relied upon as indicated on the Construction Certificate following for The Department's record.

Pursuant to Schedule 4 Item 9 of the EP&A Regulation 2021, a sum of \$44.00 for the submission of this Part 6 Certificate has been processed on the NSW Planning Portal.

Please contact the undersigned should you have any further enquiries on 02 9211 7777.

Yours sincerely,

Jackson Boyd Building Surveyor BM+G



01 September 2023

Mirvac Industrial Developments Pty Ltd Level 28, 200 George Street Sydney NSW 2000

Dear Sir/Madam

Re: DA No. SSD-10448 – 788-804 & 806-824 Mamre Road, Kemps Creek

Your recent application for a Construction Certificate dated 28.04.2023 has now been approved. We hereby enclose a copy of the Construction Certificate No. CC-23131 and associated documentation for the below:

The proposed development involves the construction of Warehouse 1 within the Aspect Industrial Estate with ancillary offices, carparking, hardstand and landscaping. **Warehouse 1 – CC2:** Building services, all external works, office fit-out, facade, excluding warehouse racking fit-out only.

We have forwarded a copy of the Construction Certificate together with the approved documentation to Council for its record.

Please also find attached an inspection and certification schedule relevant to this development. The inspection schedule identifies the necessary Statutory Mandatory Critical Stage Inspections that must be undertaken together with other inspections of the progress building works that we will require to be undertaken by our office.

It is the client's responsibility to ensure that our office is contacted with not less than 48 hours' notice for our attendance to each of these inspections.

The primary reason for these Statutory Mandatory Critical Stage Inspections is to ensure that the development proceeds in accordance with the development consent, Construction Certificates and that the development is fit for occupation in accordance with its classification under the Building Code of Australia. The Principal Certifying Authority does not undertake detailed quality control inspections. Critical Stage Inspections do not provide the level of supervision required to ensure that the minimum standards and tolerances specified by the 'Guide to Standards and Tolerances 2017 ©' are achieved.

The quality of any development is a function of the quality of the principal contractor's or owner builder's supervision of individual contractors and trades on a daily basis during the development. The PCA does not undertake this role.

The NSW Office of Fair Trading have published a 'Guide to Standards and Tolerances 2017 ©'. The guide can be obtained from the Office of Fair Trading website.

We thank you for your assistance in this matter and should you have any enquiries please do not hesitate to contact me on 9211 7777.

Yours sincerely,

Jackson Boyd Building Surveyor **BM+G**