STATION ST MENANGLE PEDESTRIAN BRIDGE CROSSING

FOR REVIEW OF ENVIRONMENTAL FACTORS (PART 5)



LOCALITY PLAN

LGA WOLLONDILLY COUNCIL LOT 11 & 2, DP 1262205 & 1262034

CLIENT:







DRAWING LIST No. DRAWING TITLE

001 GENERAL NOTES & LEGEND 002 GENERAL ARRANGEMENT PLAN

SEDIMENT & EROSION CONTROL

102 SOIL & WATER MANAGEMENT NOTES & DETAILS

ENGINEERING PLAN

302 ENGINEERING PLAN SHEET 02 OF 02

303 SITE SECTIONS

INTERSECTION DETAILS

PEDESTRIAN BRIDGE DETAILS

STATION ST MENANGLE

PEDESTRIAN BRIDGE CROSSING

17-003293.002.PED

25/05/2023

000

- ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH WOLLONDILLY SHIRE COUNCIL'S ENGINEERING DESIGN, ENGINEERING CONSTRUCTION SPECIFICATION AND TO THE REQUIREMENTS OF THE PRINCIPAL CERTIFYING AUTHORITY/ ROADS AUTHORITY
- INSPECTIONS BY PRINCIPAL CERTIFYING AUTHORITY/ ROADS AUTHORITY SHALL BE REQUESTED AT THE FOLLOWING STAGES AND THE WORKS APPROVED PRIOR TO THE CONTINUANCE OF ANY WORKS

(a) FOLLOWING THE INSTALLATION OF EROSION AND SEDIMENT CONTROL STRUCTURES/MEASURES

- (b) FINAL INSPECTIONS AFTER ALL WORKS ARE COMPLETED AND "WORK AS EXECUTED" PLANS HAVE BEEN SUBMITTED TO COUNCIL.
- G5. NO TREES TO BE REMOVED UNLESS APPROVAL IS GRANTED BY COUNCILS LANDSCAPE COMPLIANCE OFFICER/DA CONSENT.
- G6. MAKE SMOOTH JUNCTIONS WITH EXISTING WORKS
- G7. NO WORK TO BE CARRIED OUT ON COUNCIL PROPERTY OR ADJOINING PROPERTIES WITHOUT THE WRITTEN PERMISSION FROM THE
- G8. VEHICULAR ACCESS AND ALL UTILITIES/SERVICES ARE TO BE MAINTAINED AT ALL TIMES TO ADJOINING PROPERTIES AFFECTED BY CONSTRUCTION.
- ALL RUBBISH, BUILDINGS, SHEDS, AND FENCES ARE TO BE REMOVED TO THE SATISFACTION OF COUNCILS ENGINEER/SUPERINTENDENT.
- G10. COUNCIL ENGINEERS HAVE DISCRETION TO VARY, AS CONSIDERED NECESSARY, THE ENGINEERING REQUIREMENTS IN RESPECT OF PARTICULAR SUBDIVISION OR DEVELOPMENT HAVING REGARD TO THE SITE CONTEXT
- G11. ALL LEVELS REFERENCED ARE AHD.
- G12. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH WOLLONDILLY SHIRE COUNCIL SUBDIVISION & ENGINEERING STANDARD AND HAVE
 - 'WOLLONDILLY SHIRE COUNCIL CONSTRUCTION SPECIFICATION 2016'
 - 'WOLLONDILLY SHIRE COUNCIL DESIGN SPECIFICATION 2016'
 - 'WOLLONDILLY SHIRE COUNCIL STANDARD DRAWINGS 2016'
- G.13. ALL WORK WITHIN RAIL CORRIDOR TO BE CARRIED OUT IN ACCORDANCE WITH ARTC REQUIREMENTS INCLUDING ARTC'S ENVIRONMENTAL PROTECTION LICENCE.

EARTHWORKS

- EARTHWORKS ARE TO BE CARRIED OUT TO THE SATISFACTION OF THE PRINCIPAL CERTIFYING AUTHORITY/ ROADS AUTHORITY. UNSUITABLE MATERIALS ARE TO BE REMOVED FROM ROADS AND LOTS PRIOR TO FILLING. THE CONTRACTOR IS TO ARRANGE AND MAKE AVAILABLE COMPACTION TESTING RESULTS FOR ALL AREAS THAT CONTAIN FILL IN EXCESS OF 200mm
- 2. COMPACTION OF EARTHWORKS SHALL CONTINUE UNTIL A DRY DENSITY RATIO OF 95% FOR SITE FILLING AND 100% FOR ROAD PAVEMENT SUBGRADES HAS BEEN ACHIEVED IN ACCORDANCE WITH TEST METHOD AS1289.5.3.1 OR AS1289.5.1.
- THE CONTROL TESTING OF FARTHWORKS SHALL BE IN ACCORDANCE WITH THE GUIDELINES IN AS3798 "GUIDELINES ON FARTHWORKS FOR COMMERCIAL AND RESIDENTIAL DEVELOPMENTS". WHERE IT IS PROPOSED TO USE TEST METHOD AS1298.5.8.2 TO DETERMINE THE FIELD DENSITY, A SAND REPLACEMENT METHOD SHALL BE USED TO CONFIRM THE RESULTS.
- THE SUBDIVISIONALGEOTECH ACCREDITED CERTIFIER, SHALL HAVE A LEVEL1 RESPONSIBILITY FOR ALL FILLING AS DEFINED IN APPENDIX B AS3798 'GUIDELINES ON EARTHWORKS FOR COMMERCIAL AND RESIDENTIAL DEVELOPMENTS' AND AT THE END OF THE WORKS SHALL CONFIRM THE EARTHWORKS COMPLY WITH THE REQUIREMENTS OF THE SPECIFICATION AND DRAWINGS BY WRITTEN
- 5. IN AREAS TO BE FILLED WHERE THE SLOPE OF THE NATURAL SURFACE EXCEEDS 1(V):4(H), BENCHES ARE TO BE CUT TO PREVENT SLIPPING OF THE PLACED FILL MATERIAL AS REQUIRED BY THE COUNCIL
- 6. ALL BATTERS ARE TO BE SCARIFIED TO A DEPTH OF 50mm TO ASSIST THE ADHESION OF TOP SOIL TO BATTER FACE.
- PROVIDE MINIMUM 150mm AND MAXIMUM 300mm TOPSOIL WITHIN FOOTPATHS, FILLED AREAS AND ALL OTHER AREAS DISTURBED DURING CONSTRUCTION. TOPSOILED AREAS TO BE STABILISED WITH APPROVED VEGETATION A MAXIMUM OF 2 DAYS AFTER TOPSOILING AND ARE TO BE WATERED TO ENSURE GERMINATION.
- THE CONTRACTOR SHALL CONTROL SEDIMENTATION FROSION AND POLLUTION DURING CONSTRUCTION IN ACCORDANCE WITH THE REQUIREMENTS OF THE CURRENT EDITION OF 'MANAGING URBAN STORMWATER: SOILS AND CONSTRUCTION' PROVIDED BY URBAN GROWTH
- 9. EARTHWORKS TO BE SUPERVISED BY A GEOTECHNICAL ENGINEER

CALIBRE GENERAL

- CG1. SURVEY SOURCED FROM:
 - -SURVEYOR: 'ADW JOHNSON' D.T.M. & BOUNDARY: 300058-DET-004-A.dwg SURVEY DATED 27 APRIL 2021 SURVEYOR: 'ALS' : 204569-US-Menangle - DWG: LOT 202 DP590247 MENANGLE - DATED MARCH 2021 -SURVEYOR: 'ALS': 204724-US-Menangie - DWG: STATION STREET MENANGLE - DATED APRIL 2021

 NOTE: TREES SHOWN ARE INDICATIVE ONLY AND ARE A COMBINATION OF THE ABOVE SURVEY AND AERIAL IMAGING. AFRIAL IMAGE SOURCED FROM NEARMAP DATED 16/05/2021, TREES ARE TO BE VERIFIED BY PROJECT ARBORIST
- CG2. CONTRACTOR IS TO ENSURE THAT ALL WORKS ASSOCIATED WITH PROPERTY BOUNDARIES ARE TO BE SET OUT OR VERIFIED BY A REGISTERED SURVEYOR

DIGITAL MODELS CREATED BY CALIBRE UNDER THIS COMMISSION ARE CREATED FOR THE PURPOSE OF THE PREPARATION OF DRAWINGS AND ESTIMATES OF QUANTITIES. INFORMATION CONTAINED IN THE DRAWINGS TAKES PRECEDENCE OVER THE DIGITAL MODEL UPON WHICH IT WAS BASED, USE OF DIGITAL MODELS, CREATED BY CALIBRE, BY OTHER PARTIES TO SET OUT WORKS OR FOR OTHER REASONS IS DONE ENTIRELY AT THE RISK OF THE PARTY SO USING THE DIGITAL MODEL

ROADWORKS

- SUBGRADES AND SUB BASES ARE TO BE COMPACTED IN ACCORDANCE WITH COUNCIL'S CONSTRUCTION SPECIFICATION.
- R2. SUBSOIL DRAINS TO BE PROVIDED ON BOTH SIDES OF ROADS (EXCEPT WHERE THERE IS STORMWATER
- LIPLESS PERAMBULATOR CROSSINGS ARE TO BE PROVIDED IN ALL KERB RETURNS AND WHERE REQUIRED BY R3.
- R4. SERVICE CONDUITS TO BE PLACED AS DIRECTED BY ALL PUBLIC UTILITY AUTHORITIES INCLUDING ENDEAVOUR ENERGY, TELSTRA AND SYDNEY WATER
- PROPOSED UTILITIES AND SERVICES CROSSING EXISTING ROADS SHALL BE PROVIDED FOR USING A TRENCHLESS TECHNIQUE SO AS NOT TO DAMAGE THE EXISTING SURFACE. ALL SERVICE CONDUITS UNDER ROADS MUST BE LAID TO A MINIMUM DEPTH OF 750mm.
- CONCRETE FOOTPATH CONSTRUCTION IS TO FOLLOW COMPLETION OF UTILITY/SERVICES AND SURROUNDING
- ALL TEMPORARY ROADS MUST BE TEMPORARILY SEALED WITH A SINGLE COAT FLUSH SEAL.
- REFER TO PAVEMENT PLAN SHEET 601 FOR ALL PAVEMENT DETAILS.
- SIGNPOSTING AND LINE MARKING SHALL CONFORM TO AS1742.2 'TRAFFIC CONTROL DEVICES FOR GENERAL USE'. RAISED RETRO-REFLECTIVE PAVEMENT MARKERS TO CONFORM TO AS1906 'RETRO-REFLECTIVE MATERIALS AND DEVICES FOR ROAD TRAFFIC CONTROL PURPOSES', ALL APRONS AND KERB FACE ON CENTRAL SLANDS OF ROUNDABOUTS AND ALL OTHER ISLANDS TO BE DELINEATED BY REFLECTIVE WHITE MARKING. INSTALLATION SHALL OCCUR IN ACCORDANCE WITH THE PLAN APPROVED BY THE LOCAL TRAFFIC COMMITTEE
- R10 STREET SIGNS TO COUNCIL STANDARD MUST BE INSTALLED BY THE CONTRACTOR
- R11. STORMWATER PIPES IN ROAD RESERVE SHOULD BE A MINIMUM CLASS 3 RCP WITH A MINIMUM PIPE SIZE OF Ø375

STORMWATER

- S1 ALL PIPES TO BE SPIGOT AND SOCKET RUBBER RING JOINTED
- ALL LONGITUDINAL PIPELINES IN ROADS MUST BE LOCATED UNDER KERB AND GUTTER AND BE BACKFILLED WITH APPROVED GRANULAR MATERIAL UNLESS OTHERWISE APPROVED BY THE COUNCIL ENGINEER
- DRAINAGE LINES MUST BE BACKFILLED WITH APPROVED GRANULAR MATERIAL IN TRAFFICABLE AREAS. THREE (3) METRES OF SUBSOIL DRAINAGE WRAPPED IN GEOTEXTILE STOCKING MUST BE PROVIDED TO ALL
- S4. ALL GULLY PITS TO COUNCIL'S STANDARD AND LINTELS CENTRALLY PLACED AT SAG PITS.
- ALL PITS MUST BE BENCHED AND STREAMLINED, PROVIDE SL72 REINFORCEMENT AND GALVANISED STEP S5. IRONS IN ALL PITS OVER 1.2-METRES DEEP AS MEASURED FROM THE TOP OF GRATE TO THE INVERT OF THE PIT.
- CONCRETE IS TO HAVE MINIMUM COMPRESSIVE STRENGTH OF 32MPA AT 28-DAYS UNLESS OTHERWISE APPROVED BY THE COUNCIL ENGINEER.
- ALL INTER-ALLOTMENT DRAINAGE MUST HAVE A MINIMUM PIPE DIAMETER OF 150mm AND A MINIMUM GRADE OF 1% UNLESS OTHERWISE APPROVED BY THE COUNCIL ENGINEER.
- ALL INTER-ALLOTMENT DRAINAGE LINES MUST BE LAID CENTRALLY WITHIN DRAINAGE EASEMENTS. INSPECTION PITS MUST BE PROVIDED AT ALL CHANGES OF GRADE AND DIRECTION.
- INTER-ALLOTMENT DRAINAGE LINES MUST BE INSTALLED AFTER SYDNEY WATER SEWERAGE LINES HAVE BEEN INSTALLED WHERE SEWER IS PROPOSED ADJACENT TO INTER-ALLOTMENT DRAINAGE LINES.
- \$10. 1% AEP OVERLAND FLOW PATHS MUST BE FORMED AND SHOWN ON 'WORKS AS EXECUTED' DRAWINGS.
- S11. ALL PLANS (BOTH DESIGN AND WAE) ARE TO CLEARLY DELINEATE THE EXTENT/LOCATION OF FLOOD LINES INCLUDING THE 5% AEP. 1% AEP AND PMF.
- ADEQUATE PROVISION IS TO BE MADE TO PREVENT SCOURING AND SEDIMENTATION FOR ALL DRAINAGE WORKS IN ACCORDANCE WITH COUNCIL'S REQUIREMENTS.
- S13. PIT LINTELS ARE TO BE STENCILLED WITH APPLICABLE DISTINCTION STENCIL AVAILABLE FROM COUNCIL
- CATCH DRAINS MUST BE CONSTRUCTED AS REQUIRED BY THE APPROVED PLANS OR THE PRINCIPAL CERTIFYING AUTHORITY
- SOIL AND WATER MANAGEMENT PLANS ARE TO BE PREPARED FOR ALL DISTURBED SITES AND ADHERED TO AT ALL TIMES DURING THE CONSTRUCTION AND MAINTENANCE PERIODS

DESCRIPTION	PROPOSED	EXISTING	FUTURE
STORMWATER PIPELINE	375Ø		
STORMWATER DRAINAGE PITS	- □ - □		
DRAINAGE LINE No. 3 DRAINAGE PIT No. 10	(3/10)	3/10	(3/10)
CONCRETE HEADWALL	(
SUBSOIL DRAIN	—ss——ss——		
150mm KERB AND GUTTER	K&G	EXIST. K&G	FUT. K&G
450mm MODIFIED KERB AND GUTTER	M.K&G		
PEDESTRIAN RAMP	PR		41
EDGE OF BITUMEN	<u>EOB</u>	EXIST. EOB	FUT. EOB
ROAD PAVEMENT			
BENCHMARK		▲ BM: 115 RL:165.32	
BATTERS	_]_'		
CONCRETE PATHWAY			
CONTOURS	_{99,5} _{99,0}	99.5	-99.5-
SITE REGRADING AREA	CUT FILL		
SERVICE LINES SEWER, GAS, WATER, ELECTRICITY, RAIL WORKS SERVICE	S — S — W — E — RW	ex.S	fut.S — fut.G — fut.W — fut.E — fut.RW
COMMUNICATION LINES TELSTRA, FIBRE OPTIC, NBN	T OF	ex.T ————————————————————————————————————	
OVER HEAD LINES AND POLES	— ○ — OH ———	— ⊖ - ex.OH ———	—————————————————————————————————————
SERVICE PITS TELECOM PIT, ACCESS CHAMBER, HYDRANT, STOP VALVE, AIR VALVE	a 0 0 × 0		
LIMIT OF ROAD CONSTRUCTION	<u> </u>		
STAGE BOUNDARY			
LOT BOUNDARY			
EXISTING EASEMENT			
EXISTING BARRIER	—вв		
FENCE POST AND RAIL FENCE ARTC BOUNDARY FENCE	-//	RETAIN REMOVE	-//
LOT NUMBERS	D-LOTNO	E-LOTNO	F-LOTNO
	1	RETAIN REMOVE	

LEGEND

EXISTING

FUTURE

DESCRIPTION



IR	ST	DESIGN	DRAWN	CHECK	APPD.	DATE	AMENDMENT DETAILS		SCALE
S	JE	ΑV	AB/JS	CK	EF	25/02/2021	AMENDMENT DETAILS	FOR REVIEW OF ENVIRONMENTAL	
	01	ΑV	LH	CK	EF	10/06/2021	ISSUED FOR CONSTRUCTION CERTIFICATE	EACTODE (DADT 5)	
ı	02	AV	AB	CK	EF	01/07/2021	ISSUED FOR CONSTRUCTION CERTIFICATE	FACTORS (PART 5)	
ı	03	AV	AV	CK	EF	18/08/2022	ISSUED FOR CONSTRUCTION CERTIFICATE		l
ı	04	RT	SS	CK	EF	07/10/2022	ISSUED FOR CONSTRUCTION CERTIFICATE	AUTHORISED FOR ISSUE:	
ı	05	RT	AB	GM	SA	25/05/2023	ISSUED FOR REF APPROVAL	BY: SINA ARBABZADEH SIGN: Sina Anhah Zard &	

MEng (Civil) MIEAust CPEng NER

25/05/2023









GENERAL NOTES & LEGEND

NSTRUCTION. USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE. NOT 17-003293.002.PED 001 R CONSTRUCTION UNLESS STAMPED BY CERTIFYING AUTHORITY

REF

05






SEDIMENT & EROSION CONTROL NOTES

- THE CONTRACTOR SHALL IMPLEMENT ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES IN ACCORDANCE WITH ARTC'S ENVIRONMENTAL PROTECTION LICENCE (SECTION 55 PROTECTION OF THE ENVIRONMENT OPERATIONS ACT 1997) FOR WORKS WITHIN THE RAIL CORRIDOR
- 2. THE CONTRACTOR SHALL IMPLEMENT ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES PRIOR TO THE COMMENCEMENT OF ANY WORKS BEING CARRIED OUT. ALL SOIL AND EROSION MEASURES SHALL BE MAINTAINED AND KEPT IN PLACE FOR THE FULL DURATION OF THE WORKS AND SHALL ONLY BE REMOVED AT FINAL STABILISATION OF THE WORKS. WHERE IT IS NECESSARY TO UNDERTAKE STRIPPING IN ORDER TO CONSTRUCT A SEDIMENT CONTROL DEVICE ONLY SUFFICIENT GROUND SHALL BE STRIPPED TO ALLOW CONSTRUCTION.
- ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CONSTRUCTED & MAINTAINED AS INDICATED ON THESE DRAWINGS AT A MINIMUM LOCATION AND EXTENT OF SOIL & WATER MANAGEMENT DEVICES IS DIAGRAMMATIC ONLY AND THE ACTUAL REQUIREMENTS SHALL BE CONFIRMED ON SITE PRIOR TO COMMENCEMENT.
- CONFORMITY WITH THIS PLAN SHALL IN NO WAY REDUCE THE RESPONSIBILITY OF THE CONTRACTOR TO PROTECT AGAINST WATER DAMAGE DURING THE COURSE OF THE CONTRACT, IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO ENSURE THAT ANY NECESSARY CONTROL IS IN PLACE EVEN THOUGH SUCH CONTROL MAY NOT BE SHOWN ON THE PLAN.
- THE CONTRACTOR SHALL INFORM ALL SUBCONTRACTORS & ALL EMPLOYEES OF THEIR RESPONSIBILITIES IN MINIMISING THE POTENTIAL FOR SOIL EROSION & POLLUTION TO DOWNSTREAM AREAS
- APART FROM SEDIMENT BASINS, THE CONTRACTOR SHALL REGULARLY MAINTAIN SEDIMENT AND EROSION CONTROL STRUCTURES & DESILT SLICH STRUCTURES PRIOR TO THE REDUCTION IN CAPACITY OF 30% DUE TO ACCUMULATED SEDIMENT. THE SEDIMENT SHALL BE DISPOSED OF ON SITE IN A MANNER APPROVED BY THE ENGINEER.
- THE CONTRACTOR SHALLTEMPORARILY REHABILITATE WITHIN TEN (10) DAYS ANY DISTURBED AREAS PROVIDING A MINIMUM 60% COVER. FINAL REHABILITATION IS TO BE PROVIDED WITHIN A FURTHER 60 DAYS WITH A
- THE CONTRACTOR SHALL PROVIDE WATERING OF THE VEGETATED BATTERS FOR MAINTENANCE PERIOD, PLANT, MACHINERY AND VEHICLES SHALL NOT BE DRIVEN OVER GRASSED AREAS UNLESS ON AN APPROVED HAULAGE ROUTE.
- 9. ALL DRAINAGE WORKS SHALL BE CONSTRUCTED AND STABILISED AS QUICKLY AS POSSIBLE TO MINIMISE RISK OF EROSION
- 10. SITE ACCESS SHALL BE RESTRICTED TO THE NOMINATED POINTS. THE CONTRACTOR SHALL PROVIDE STABILISED SITE ACCESS
- 11. DUST AND SITE DISTURBANCE MUST BE KEPT TO A MINIMUM. DURING WINDY WEATHER, LARGE, UNPROTECTED AREAS MUST BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO REDUCE WIND EROSION. ERECT BARRIER FENCING TO MINIMISE LAND DISTURBANCE BY PREVENTING VEHICULAR AND PEDESTRIAN ACCESS TO AREAS BEING REHABILATATED AND LANDS THAT DO NOT NEED TO BE DISTURBED BY
- 12. STOCKPILE TOPSOILS, SUBSOILS AND OTHER MATERIALS SEPARATELY.
- 13. TOPSOIL SHALL BE STORED IN LOW MOUNDS NO MORE THAN 2 METRES. HIGH AND RE-USED WITHIN TWO MONTHS TO MAINTAIN ACTIVE POPULATIONS OF BENEFICIAL SOIL MICROBES & SEED
- 14. PLACE ALL STOCKPILES AT LEAST FIVE METRES FROM AREAS OF LIKELY CONCENTRATED OR HIGH VELOCITY FLOWS, ESPECIALLY EARTH BANKS AND ROADS IF NECESSARY FARTH BANKS OR DRAINS WILL BE CONSTRUCTED TO DIVERT LOCALISED RUN-ON
- 15. TURN TOPSOIL STOCKPILES OVER TO AERATE THEM AT MONTHLY INTERVALS. ENSURE VEGETATION IS NOT INCORPORATED INTO THE SOIL

- 16 AVOID REVERSING THE SOIL PROFILE MATERIALS DURING FILL OPERATIONS - REPLACE DISTURBED SOILS IN THEIR ORIGINAL ORDER.
- ON COMPLETION OF MAJOR EARTHWORKS AND BEFORE ADDING TOPSOIL, LEAVE DISTURBED LANDS WITH A LOOSE SURFACE. ALTERNATELY, DISTURBED AREAS PREVIOUSLY COMPACTED BY CONSTRUCTION WORKS WILL BE RIPPED TO MORE THAN 200mm ALONG THE CONTOUR BEFORE
- PROVIDING MATERIALS ARE AVAILABLE, SPREAD TOPSOIL TO A MINIMUM DEPTH OF 75mm IN REVEGETATION AREAS ON SLOPES OF 4(H):1(V) OR LESS AND TO A DEPTH OF 40 TO 60mm IN REVEGETATION AREAS STEEPER
- 19. LEAVE TOPSOIL IN A SCARIFIED OR ROUGH CONDITION ONCE REPLACED TO HELP MOISTURE INFILTRATION AND REDUCE SOIL EROSION.
- 20. ENSURE SOIL IS THOROUGHLY SOAKED TO A DEPTH OF 75mm (RAIN OR IRRIGATION) IMMEDIATELY BEFORE PLANTING.
- 21. HANDLE TOPSOIL ONLY WHEN IT IS MOIST (NOT WET OR DRY) TO AVOID DECLINE OF SOIL STRUCTURE
- 22. THE CONTRACTOR SHALL MAINTAIN A LOG BOOK DETAILING: RECORDS OF ALL RAINFALL
 - CONDITION OF SOIL AND WATER MANAGEMENT STRUCTURES
- ANY APPLICATION OF FLOCCULATING AGENTS TO SEDIMENT BASIN VOLUMES OF ALL WATER DISCHARGED FROM SEDIMENT BASINS - ANY ADDITIONAL REMEDIAL WORKS REQUIRED
- 23. THE LOG BOOK SHALL BE MAINTAINED ON A WEEKLY BASIS AND RE MADE AVAILABLE TO ANY AUTHORISED PERSON UPON REQUEST. THE ORIGINAL LOG BOOK SHALL BE ISSUED TO THE PROJECT MANAGER AT THE
- 24. ALL ROAD EMBANKMENTS TO BE STABILISED AS PER LANDSCAPE ARCHITECTS DETAILS.
- 25. A SELF AUDITING PROGRAM SHOULD BE ESTABLISHED BASED ON A CHECK SHEET DEVELOPED FOR THE SITE. A SITE INSPECTION USING THE CHECK SHEET SHOULD BE MADE BY THE SITE MANAGER AT LEAST WEEKLY, IMMEDIATELY BEFORE SITE CLOSURE AND IMMEDIATELY FOLLOWING RAINFALL EVENTS THAT CAUSE RUNOFF.
- 26. UNDERTAKE THE SELF AUDIT BY:
 - WALKING AROUND THE SITE SYSTEMATICALLY (E.G. CLOCKWISE)
 - RECORDING THE CONDITION OF EVERY BMP EMPLOYED
 RECORDING MAINTENANCE REQUIREMENTS (IF ANY) FOR EACH BMP

 - RECORDING THE SITE WHERE SEDIMENT IS DISPOSED
 FORWARDING A SIGNED DUPLICATE OF THE COMPLETED CHECK SHEET
 - TO THE PROJECT MANAGER/DEVELOPER/SITE OPERATOR FOR THEIR INFORMATION
- 27. IN PARTICULAR, INSPECT:
- LOCATIONS WHERE VEHICLES ENTER AND LEAVE THE SITE ALL INSTALLED EROSION AND SEDIMENT CONTROL MEASURES, ENSURING THEY ARE OPERATING CORRECTLY - AREAS THAT MIGHT SHOW WHETHER SEDIMENT OR OTHER
- POLLUTANTS ARE LEAVING THE SITE OR HAVE POTENTIAL TO DO SO - ALL DISCHARGE POINTS, TO ASSESS WHETHER THE EROSION AND SEDIMENT CONTROL MEASURES ARE EFFECTIVE IN PREVENTING. IMPACTS TO THE RECEIVING WATERS
- 28. A SITE INSPECTION USING THE CHECK SHEET WILL BE MADE BY THE SITE MANAGER AT LEAST WEEKLY, IMMEDIATELY BEFORE SITE CLOSURE, AND IMMEDIATELY FOLLOWING RAINFALL EVENTS GREATER THAN 5mm IN 24 HOURS.



CONSTRUCTION NOTES: 1. CONSTRUCT SEDIMENT FENCES AS CLOSE AS POSSIBLE TO BEING PARALLEL TO THE CONTOURS OF

- THE SITE. BUT WITH SMALL RETURNS AS SHOWN IN THE DRAWING TO LIMIT THE CATCHMENT AREA OF THE SITE, BOT WITH SWILL RELIDING AS SHOWN IN THE DRAWING TO LIMIT THE CATCHMENT AREA OF ANY ONE SECTION. THE CATCHMENT AREA SHOULD BE SMALL ENOUGH TO LIMIT WATER FLOW IF CONCENTRATED AT ONE POINT TO 50 LITRES PER SECOND IN THE DESIGN STORM EVENT, USUALLY THE 10-YEAR EVENT.

 2. CUT A 150-mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE
- FABRIC TO BE ENTRENCHED.

 3. DRIVE 1.5 METRE LONG STAR PICKETS INTO GROUND AT 2.5 METRE INTERVALS (MAX) AT THE
- DOWNSLOPE FDGE OF THE TRENCH. ENSURE ANY STAR PICKETS ARE FITTED WITH SAFETY CAPS. DOWNSLOPE EDGE OF THE TRENCH. ENSURE ANY STAR PICKETS ARE FITTED WITH SAFETY CAPS.

 4. FIX SELF-SUPPORTING GEOTEXTILE TO THE UPSLOPE SIDE OF THE POSTS ENSURING IT GOES TO THE

 BASE OF THE TRENCH. FIX THE GEOTEXTILE WITH WIRE TIES OR AS RECOMMENDED BY THE

 MANUFACTURER. ONLY USE GEOTEXTILE SPECIFICALLY PRODUCED FOR SEDIMENT FENCING. THE USE

 OF SHADE CLOTH FOR THIS PURPOSE IS NOT SATISFACTORY.


 5. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150-mm OVERLAP.

 6. BACKFILL THE TRENCH OVER THE BASE OF THE FABRIC AND COMPACT IT THOROUGHLY OVER THE

 GEOTEXTIE.

SD 6-8

SEDIMENT FENCE



CONSTRUCTION NOTES:

PLACE STOCKPILES MORE THAN 2 (PREFERABLY 5) METRES FROM EXISTING VEGETATION CONCENTRATED WATER FLOW, ROADS AND HAZARD AREAS.

CONSTRUCT ON THE CONTOUR AS LOW, FLAT, FLONGATED MOUNDS


CONSTRUCT ON THE CONTOUR AS LOW, FLAT, ELONGATED MOUNDS.
 WHERE THERE IS SUFFICIENT AREA, TOPSOIL STOCKPILES SHALL BE LESS THAN 2 METRES IN HEIGHT.
 ALL STOCKPILES ARE TO BE LOCATED AND PLACED IN ACCORDANCE WITH THE CONTRACTOR'S EROSION AND SEDIMENT CONTROL PLAN.
 WHERE STOCKPILES ARE TEMPORARY (<14 DAYS) NO STABILISATION IS REQUIRED. REVIEW THE ADEQUACY OF SEDIMENT CONTROLS IF RAINFALL IS PREDICTED.
 WHERE STOCKPILES ARE TEMPORARY (<14 DAYS) THE FOLLOWING ADDITIONAL CONTROLS ARE DECUIRED.

REQUIRED: -MAXIMUM BATTER SLOPE REDUCED TO 1:4

CONSTRUCT A CONTOUR DRAIN ON THE LOW SIDE OF THE STOCKPILE, AND DISCHARGING THROUGH A STRAW BALE OR 200mm HIGH GRAVEL DAM -ESTABLISH GRASS COVER TO SURFACE OF STOCKPILE WITHIN 14 DAYS, USING HYDROMULCH WITH A 75.25 MIX OF SEASONAL AND PERMANENT GRASS SEEDS, AND A STRAW MULCH THICKNESS OF NO

CONSTRUCT EARTH BANKS (STANDARD DRAWING 5-5) ON THE UPSLOPE SIDE TO DIVERT WATER AROUND STOCKPILES AND SEDIMENT FENCES (STANDARD DRAWING 6-8) 1 TO 2 METRES DOWNSLOPE

STOCKPILES SD 4-1



2. FOLLOW STANDARD DRAWING 6-7 AND STANDARD DRAWING 6-8 FOR INSTALLATION PROCEDURES FOR THE STRAW BALES OR GEOFABRIC REDUCE THE PICKET SPACING TO 1 METRE CENTRES. 3. IN WATERWAYS, ARTIFICIAL SAG POINTS CAN BE CREATED WITH SANDBAGS OR EARTH BANKS AS

A DO NOT COVER THE INLET WITH GEOTEXTILE UNLESS THE DESIGN IS ADEQUATE TO ALLOW FOR ALL WATERS TO BYPASS IT.

GEOTEXTILE INLET FILTER

SD 6-12

FOR REVIEW OF ENVIRONMENTAL AV AB/JS CK EF 25/02/20 01 AV LH CK EF 1 FACTORS (PART 5) SUED FOR CONSTRUCTION CERTIFICATE AV AV CK EF ITHORISED FOR ISSUE: RT SS CK EF RT AB GM SA SUED FOR CONSTRUCTION CERTIFICATE BY: SINA ARBABZADEH SIGN: Sina Antholo Zord et SUED FOR REF APPROVAL DATE: MEng (Civil) MIEAust CPEng NER






© 2023


STATION ST MENANGLE PEDESTRIAN BRIDGE CROSSING


SOIL & WATER MANAGEMENT **NOTES & DETAILS**


ISTRUCTION. USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE NOT CONSTRUCTION UNLESS STAMPED BY CERTIFYING AUTHORITY 17-003293.002.PED 102


05 REF














	FIRST	DESIGN	DRAWN	CHECK	APPD.	DATE	AMENDMENT DETAILS		SC
5	ISSUE	AV	AB/JS	CK	EF	25/02/2021	AMENDMENT DETAILS	FOR REVIEW OF ENVIRONMENTAL	
ź	_A 01	AV	LH	CK	EF	10/06/2021	ISSUED FOR CONSTRUCTION CERTIFICATE	EACTODE (DADT 5)	
5	M 02	AV	AB	CK	EF	01/07/2021	ISSUED FOR CONSTRUCTION CERTIFICATE	FACTORS (PART 5)	
2	N 03	AV	AV	CK	EF	18/08/2022	ISSUED FOR CONSTRUCTION CERTIFICATE		
3	м 04	RT	SS	CK	EF	07/10/2022	ISSUED FOR CONSTRUCTION CERTIFICATE	AUTHORISED FOR ISSUE:	
Ì	E 05	RT	AB	GM	SA	25/05/2023	ISSUED FOR REF APPROVAL	BY: SINA ARBABZADEH SIGN: Simu Anhuh Zarol &	
ŝ	Ţ							MEng (Civil) MIEAust CPEng NER 25/05/2023	
į	١							DATE:	








MEC!	DRA
STATION ST MENANGLE	S
PEDESTRIAN BRIDGE CROSSING	

	TE SE	CTIONS		
PROJE	CT No.	DRAWING No.	MILESTONE	

ISCLAIMER

IL DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR PRIOR TO
ONSTRUCTION. USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE. NOT
DR CONSTRUCTION UNLESS STAMPED BY CERTIFYING AUTHORITY

PROJECT No.	DRA	AWING No.	MILESTONE	REVISION
17-003293.002.P	ED	303	REF	05



PAVEMENT JOINTING LEGEND

EXPANSION JOINT. REFER COUNCIL

SAWN JOINT. REFER COUNCIL STANDARD DRAWING No.WSC.D2.2

PAVEMENT DETAILS LEGEND

WEARING COURSE - 50mm AC14 (2x25mm LAYERS)
SEAL - SINGLE COAT FLUSH SEAL WEARI SEAL BASE COURSE - 150mm DGB20 SUB BASE COURSE - 340mm CRUSHED BASE COURSE

SANDSTONE (75mm - 4%

CONCRETE FOOTPATH AND PRAM RAMP CROSSING. 125mm THICK 25MPa WITH SL82 REINFORCING MESH (CENTRAL) ON 75mm (MIN. OF COMPACTED ROAD SUB-BASE

PAVEMENT NOTES:

1. ADOPTED TRAFFIC LOADINGS: STATION STREET - 2x10⁶

2. PAVEMENT DESIGN PREPARED BY GEOTECHNIQUE JOB No 14305/11 DATED 7TH JUNE 2021

3. ALL PAVEMENT DESIGNS ARE SUBJECT TO GEOTECHNICAL TESTING & DESIGN DURING CONSTRUCTION

4. CONCRETE PAVEMENT & DRIVEWAY FINISH TO BE CONFIRMED BY SUPERINTENDENT OR LANDSCAPE ARCHITECT AT TIME OF CONSTRUCTION.

PAVEMENT JOINTING NOTES

- ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH AS3600(2018) AND AS4678(2002).
- COMPRESSIVE STRENGTH (F'c) FOR CAST IN SITU CONCRETE SHALL BE A MINIMUM 25MPa AT 28 DAYS.
- MAXIMUM CONCRETE AGGREGATE SIZE TO BE 20mm UNLESS STATED
- NO ADMIXTURES SHALL BE USED IN CONCRETE UNLESS APPROVED IN
- ALL CONCRETE FORMWORK SHALL BE DESIGNED, ERECTED, SUPPORTED, BRACED AND MAINTAINED IN ACCORDANCE WITH AS3610(2018).
- NO HOLES, CHASES OR EMBEDMENT OF PIPES OTHER THAN THOSE SHOWN ON THE STRUCTURAL DRAWINGS SHALL BE MADE IN CONCRETE
- MEMBERS WITHOUT THE PRIOR WRITTEN APPROVAL OF THE ENGINEER. CONDUITS, PIPES, ETC. SHALL ONLY BE LOCATED IN THE MIDDLE THIRD OF THE SLAB DEPTH. PIPES OR CONDUITS SHALL NOT BE PLACED WITHIN THE COVER TO REINFORCEMENT
- SIZES OF CONCRETE MEMBERS DO NOT INCLUDE THE THICKNESS OF
- APPLIED FINISHES REFER TO THE ARCHITECTS DRAWINGS FOR ALL SLAB FALLS AND
- CONFIRMATION OF SLAB STEPS.
 CONSTRUCTION JOINTS SHALL BE LOCATED TO THE APPROVAL OF THE
- 11. SAW CUT JOINTS IN SLABS ON GROUND AS EARLY AS POSSIBLE WITHOUT CAUSING UNACCEPTABLE RAVELLING OF JOINT EDGES
- (NORMALLY WITHIN 24 HOURS OF CASTING SLAB). COMPLETE SAW CUTTING WITHIN 36 HOURS OF CASTING SLAB. INITIATE AN APPROVED METHOD OF CURING FOR ALL CONCRETE ELEMENTS AS SOON AS PRACTICABLE AFTER THE CONCRETE HAS SET
- AND MAINTAIN IT FOR AT LEAST 7 DAYS. CURING OF CONCRETE IS TO BE ACHIEVED BY KEEPING SURFACES CONTINUOUSLY WET FOR A PERIOD OF 3 DAYS, AND PREVENTION OF LOSS OF MOISTURE FOR A TOTAL OF 7 DAYS FOLLOWED BY A GRADUAL
- WHEN CONCRETING DURING HOT (MORE THAN 25°) AND/OR WINDY CONDITIONS, APPLY ALIPHATIC ALCOHOL TO HORIZONTAL ELEMENTS
- FOR CONCRETE PAVEMENT REINFORCEMENT DETAILS REFER TO CALIBRE PAVEMENT PLAN, COUNCIL SPECIFICATION, AND/OR RELEVANT LANDSCAPE ARCHITECT DRAWING(S).

SCALE 1:200 (A1)

MEng (Civil) MIEAust CPEng NER

0 0.1 0.2 0.3 0.4 0.5 0.6 0.7 0.8

2.0 4.0 6.0 8.0 10.0 12.0 14.0 16.0


2.4 2.8 3.2

SCALE 1:80 (A3)

SCALE 1:200 (A3)


SCALE 1:400 (A3)

0.4 0.8 1.2 1.6



PAVEMENT SAWCUT JOINT DETAIL FOR KERB & SUBSOIL INSTALLATION

PAVEMENT TRAVERSE JOINT WITH EXISTING PAVEMENT SCALE 1:10



KERB RETURN No.01

SCALE 1:200 (H) SCALE 1:40 (V)






© 2023

INTERSECTION PLAN & DETAILS STATION ST MENANGLE PEDESTRIAN BRIDGE CROSSING

0	PROJECT No.	DRAWING No.	MILESTONE	REVISION
<u>OT</u>	17-003293.002.PED	601	REF	05



DRAINAGE PIT SETOUT TABLE							
Point Pit No. Pit Type Easting Northing							
1	01/1	G.G.P. 1.2m E.K.I.	284385.037	6213020.977			
2	01/2	G.S.I.P. 900x900	291836.509	6221441.770			
3	01/3	G.G.P. 1.8m E.K.I.	291833.898	6221449.595			



LINE No.01

DRAINAGE LONGITUDINAL SECTION

SCALE 1:500 (H) SCALE 1:100 (V)


NOTES:

- 1. RRJ3 DENOTES RUBBER RING JOINT CLASS 3 PIPE
- 2. ALL PVC PIPE TO BE CLASS SH.
- 3. PITS TO BE CONCRETE REINFORCED AS PER WOLLONDILLY SHIRE COUNCIL STD DWG STANDARD GRATED KERB INLET PIT WSC.D5.10.
- 4. PITS DEEPER THAN 3.0m, AND GREATER THAN 2.0m IN INTERNAL DIMSENSION ARE TO BE STRUCTURALLY DESIGNED.
- CONCRETE 32MPa COMPRESSIVE STRENGTH AT 28 DAYS.

PIT TYPE:

- G.G.P. GRATED GULLY PIT G.S.I.P. GRATED SURFACE INLET PIT J.P. JUNCTION PIT H.W. HEADWALL

- D.C. DIRECT CONNECTION S.J. SLOPE JUNCTION BEND BEND IN LINE
- GPT GROSS POLLUTANT TRAP



-SETOUT POINT

JUNCTION PIT

TYPICAL PIT SETOUT DETAIL N.T.S

PLAN
SCALE 1:100

MEng (Civil) MIEAust CPEng NER

25/05/2023

RST	DESIGN	DRAWN	CHECK	APPD.	DATE	AMENDMENT DETAILS	STATUS
SUE	AV	AB/JS	CK	EF	25/02/2021	AMENDMENT DETAILS	FOR REVIEW OF ENVIRONMENTAL
01	AV	LH	CK	EF	10/06/2021	ISSUED FOR CONSTRUCTION CERTIFICATE	EACTODS (DADT 5)
02	AV	AB	CK	EF	01/07/2021	ISSUED FOR CONSTRUCTION CERTIFICATE	FACTORS (PART 5)
03	AV	AV	CK	EF	18/08/2022	ISSUED FOR CONSTRUCTION CERTIFICATE	
04	RT	SS	CK	EF	07/10/2022	ISSUED FOR CONSTRUCTION CERTIFICATE	AUTHORISED FOR ISSUE:
05	RT	AB	GM	SA	25/05/2023	ISSUED FOR REF APPROVAL	BY: SINA ARBABZADEH SIGN: Sina Anhah Zarolah


SUBSOIL TO -

CONNECT INTO PIT

UNDER BORE PIPE IN VICINITY OF TREE. WORKS

LEVEL 5 PROJECT ARBORIST

MUST BE UNDERTAKEN UNDER SUPERVISION OF COUNCIL TREE PROTECTION OFFICER AND A



ALL EXCAVATION WORKS WITHIN TPZ OF TREE TO BE UNDERTAKEN IN THE PRESENCE OF RAIL AUTHORITY AND/OR ARBORIST (LEVEL 5) AT RAIL AUTHORITY'S

LEGEND

07/05/2021

DISCRETION. TREE MUST BE PROTECTED AND PRESERVED THROUGHOUT CONSTRUCTION PHASE.

TREE TO BE RETAINED & PROTECTED

DBH AS PER ARBORIST'S REPORT STURT NOBLE ARBORICULTURE DATED

STURT NOBLE ARBORICULTURE DATED

SRZ AS PER ARBORIST'S REPORT

MAKE SMOOTH CONNECTION INTO EXISTING

DRAINAGE SYSTEM PROPOSED UNDER MENANGLE STAGE 1 (REF. DA-010.2019.000000093.001)





STATION ST MENANGLE
PEDESTRIAN BRIDGE CROSSING

DRAINAGE PLAN ١G

SCLAIMER

L DIMENSIONS TO BE CHECKED ON SITE BY CONTRACTOR PRIOR TO
DNSTRUCTION. USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE, NOT
DR CONSTRUCTION UNLESS STAMPED BY CERTIFYING AUTHORITY

ROJECT No.	DRAV	VING No.	MILESTONE	REVISION
17-003293.002.PI	ED	801	REF	05

